Bruhat Bangalore Mahanagara Palike
Excecutive Engineer Project Division Yelahanka

Name of Work: Improvements to Roads and Drains in Vinayakanagara, Kattigenahalli and Dwarakanagara Surrounding area in Ward No: 05

Modified Schedule - B

Sl No	Description of Item	Unit	Quantity	Rate, Rs	
				In Figures	In Words
1	KSRRB 300 - Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (P.No-143, I.No-19.1)	Cum	14902.40	201.31	Rupees Two Hundred One And Paise Thirty One Only
2	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222,I No-27.18)	Cum	2007.33	5892.00	Rupees Five Thousand Eight Hundred Ninety Two Only
3	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specificationsdo- Wall & bottom thickness 15cm (I No-37.59.2,P No-271,KPWD SR 2018-19)	Cum	3890.17	7394.46	Rupees Seven Thousand Three Hundred Ninety Four And Paise Forty Six Only
4	KSRRB M2200-6. Providing T.M.T. steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per disign (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification. MORTH Specification No.1600 & 2200(I No-28.8.2,P No-229)	Tn	237.91	70704.00	Rupees Seventy Thousand Seven Hundred Four Only

Scanned by TapScanner

S. No	Description of Item	Unit	Quantity	Rate, Rs	
				In Figures	In Words
5	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M30 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and	Sqm	9584.34	2358.60	Rupees Two Thousand Two Hundred Fifty Eight And Paise Sixty Only
6	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of all materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge. (Data Rate)	Sqm	337.50	5267.87	Rupees Five Thousand Two Hundred Sixty Seven And Paise Eighty Seven Only
	Above 125%	Sqm	69.21	5267.87	Rupees Five Thousand Two Hundred Sixty Seven And Paise Eighty Seven Only
	EIRL				Rupees Nil
E1	KSRB 2-2 : Earthwork excavation by manual means for foundation of buildings, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods	Cum	495.90	320.11	Rupees Three Hundred Twenty And Paise Eleven Only
E2	PVC Pipes 10KG/Sqm 90mm outerdia, (Code no-3001,Sl no-885,P No-XXXIV)	M	551.00	317.55	Rupees Three Hundred Seventeen And Paise Fifty Five Only
E3	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications	Cum	495.90	129.54	Rupees One Hundred Twenty Nine And Paise Fifty Four Only

Executive Engineer,
Yelahanka Project Division,
BBMP Bangalore

Scanned by TapScanner